Preliminary Description of Materials & Finishes

Finish selections for all units have been made by the Developer & will be installed as specified.

All information furnished in the specifications is subject to change based on site conditions, construction tolerances or other conditions without notice. In the case of discrepancies between specifications and the field, the field shall govern.

Please note due to the supply chain shortages, longer production and shipping times, the Developer is experiencing challenges with material and fixtures and reserves the right to make replacements of like kind & quality for any item that may be back ordered, out of stock or discontinued.

All finishes have been selected by the Developer and will be installed as specified.

Date_____

FINISHES	Cabinetry	Flat Panel style cabinetry, Matte Black finish on wall cabinets, Oak textured laminate finish on island & back island panel. Island has extended side panels.		
	Cabinet Hardware	Matte Black Edge pulls		
	Countertop	$1\mbox{\ensuremath{\mbox{\ensuremath{\mbox{\sc H}}}}\xspace}$ Quartz options with square polished edge, 10-12" Breakfast Bar overhang at island.		
	Backsplash	Developer's included backsplash tile, installed from the countertop to the bottom of the upper cabinets and the hood cabinet.		
PLUMBING FIXTURES &	Faucet	Delta Trinsic, single handle with pull-down spray, Matte Black finish, Model 9159-BL-DST		
AMENITIES	Sink	Single bowl, rectangular under mount, Stainless Steel.		
	Disposal	1/2 HP garbage disposal.		
	Under Cabinet Lighting	LED strip lighting installed under upper cabinets.		
APPLIANCES Refrigerator Duplexes		Thermador, 36", Freedom Collection Panel Ready With Bottom Freezer, Model T36BB925SS, Cabinet Door Panels, Matching Wall Cabinets.		
	Refrigerator Simplexes	Thermador, 36", Freedom Collection Panel Ready With Bottom Freezer, Model T36BB925SS, Stainless Steel Door Panels.		
	Range	Thermador 36" Pro Harmony (6) Burner Gas Range, Model PRG366WHSS, Stainless Steel.		
	Hood	Best 28" Built In Range Hood, Model P1952MS70SB		
	Dishwasher	Thermador Emerald Built-In Dishwasher with Pro Handles, Model DWHD650WFPSS, Stainless Steel.		

1

The **Biazar** Group

NORTH CLYBOURN GROUP

Microwave Thermador 24" Masterpiece & Professional Series Micro Drawer, Model MD24WSS

LAUNDRY

Washer LG, White Front Loading Ultra Large Washer, Model #WM4000HWH.

Dryer LG, White Front Loading Ultra Large Dryer, Model #DLGX4001WH.

PRIMARY BATH

FINISHES

Double Floating

Vanity

Flat Panel style vanity cabinet, Matte White Finish

Cabinet Hardware

Shower Fixtures

Developer's included pulls with cupboard handles, Brushed Brass finish.

Countertop

1 1/4" Quartz options with square polished edge with 4" quartz backsplash.

Sink

Rectangular white vessel sink

TILE

PLUMBING FIXTURES & AMENITIES

Faucets (2) Vigo Norfolk single hole faucet, Model VG03027BN, Brushed Nickel finish

Sink Rectangular white vessel sink

Shower Walk in Steam Shower with built in bench and shower niche.

Gerber Amalfi temperature valve trim, Model D510430BNTC, Gerber Amalfi diverter valve trim, Model D560930BNT, Gerber Parma, 5 function handshower with Versa 30" slide bar, Model D461728BN, Gerber Drench 8" rain showerhead, Model D46006,

Brush Nickel finish

Shower Door3/8" frameless clear glass door, approximately 7' in height, installed with glass header

to the ceiling.

Toilet 2 piece, White.

Mirror (2) Uttermost 28" Alexo square mirror, Brushed Gold finish

Lighting Per lighting section

Heated Floors

Heated floors included in Prmary bath, excludes shower base and area under vanity

cabinet and toilet.

Bath Accessories Toilet paper holder, towel bars not included.

Buyer	10/7/2022	Seller
Date	2	Date

^{*}Tile selections specified by Developer, installed at shower walls to ceiling, shower ceiling, shower bench, shower niche, shower floor, & bathroom floor.

GUEST BATH

FINISHES

Single Vanity Flat Panel style vanity cabinet, Matte Black Finish

Cabinet Hardware Developer's included pulls with cupboard handles, Brushed Brass finish.

Countertop 1 1/4" Quartz options with square polished edge with 4" quartz backsplash.

TILE

*Tile selections specified by Developer, installed standard height at tub walls, & on bathroom floor.

PLUMBING FIXTURES & AMENITIES

Faucet (1) Vigo Norfolk single hole faucet, Model VG03027BN, Brushed Nickel finish

Sink Rectangular white vessel sink

Tub Built in tub with white apron front.

Tub FixturesGerber Amalfi tub & showerhead, diverter valve trim and tub filler, Model

D512030BNTC, Brushed Nickel finish

Toilet 2 piece, White.

Mirror 24" - 28" Round mirror, Black finish

Lighting Per lighting section.

Bath Accessories Toilet paper holder, towel bars not included.

POWDER ROOM

FINISHES

Single Floating

Vanity

Flat Panel style vanity cabinet, Oak Textured Laminate Finish

Cabinet Hardware

Developer's included pulls with cupboard handles, Mate Black finish.

Countertop

1 1/4" Quartz options with square polished edge with 4" quartz backsplash.

PLUMBING FIXTURES & AMENITIES

Faucet (1) Vigo Norfolk single hole faucet, Model VG03027BN, Brushed Nickel finish

Sink Rectangular white vessel sink

Toilet 2 piece, White.

Mirror Savina 36" x 18" Modern & Contemporary Rectangular mirror, Black finish

Lighting Per lighting section.

Bath Accessories Toilet paper holder, towel bars not included.

Buyer	10/7/2022	Seller
Date	3	Date

FLOORING

Hardwood

Boen 5 -7/16" wide plank Oak pre finished hardwood flooring, Warm Gray Oak finish. Installed throughout all units less the lower level . Excludes bathrooms, laundry and mechanical closets.

Heated Floors Duplex Down Units Electric heated floors included in duplex down units. Heated floors are separated in 3 different zones, Primary Bed/ Bath Suite (1 zone), Guest Bath (1 zone), Family Room & Hallway (1 zone).

Lower Level Duplex Down Units

Oversized Porcelain tile to be installed in the lower level family room and lower level hallway. Carpet to be installed in the lower level bedrooms.

Laundry & Mechanical Closets

Developer's selected tile.

PAINT

Sherwin Williams Snowbound, SW 7004. Walls, flat finish throughout, except bathrooms. Bathrooms, eggshell finish, Doors and trim, and ceilings, Developer's included White. Trim, semi gloss finish, ceilings, flat finish.

CLOSETS

Primary Bedroom

Developer provided custom closet organizers.

Guest Beds & Coat Closets

Melamine Shelf and rod installation.

LIGHTING

RECESSED CANS

Locations

Recessed can lighting installed in: Kitchen, Living Room Hallways, Primary Bedroom, Primary Bath, Guest Bath, Family Room of Duplex Units.

SURFACE MOUNTED

Kitchen Island

Primary Bathroom

(1) Modern Minimalist 10-Light Glass Globe Shade Kitchen Island Light, Black finish

(2) Wall mounted vanity fixtures.

Guest Bath

(1) Hinley Seeded Glass, 3 Light Vanity light, Polished Nickel & Black finish

Buyer _.	 	 	
Date			

10/7/2022

Seller_____Date

4

The Biazar Group

NORTH CLYBOURN GROUP

Powder Room (2) Tara Wall Sconces, Model H116101-AGB, Aged Brass finish

(1) Progress Lighting Inspire, 13" flush mount drum ceiling fixture, Model **Guest Bedrooms**

P350130-009, Brushed Nickel finish

(2-3) Tara Wall Sconces, Model H116101-OB, Old Bronze finish, at the **Stairwell Sconces**

interior stairwells of the duplex units.

Junction Box for Future Use

(1) ceiling mounted junction box provided for future use in Primary Bedroom.

DOORS

Bldg Main Entry Full lite commercial grade glass door

Front Unit Entry

Doors

Flat Panel steel, painted white

Rear Unit Entry

Doors

Per plan

Balcony & Roof Access Doors

Schuco, full lite glass door with black frame

Interior Doors

7'-6" Solid core single panel, Shaker Style, painted white. Mechanical doors

will be vented

Interior Door Hardware

Single lever handles, Brushed Nickel finish on handles and hinges

TRIM

Door & Window

Casing

3 1/4" flat profile casing, painted white

Baseboards

5 1/4" flat profile base trim, painted white

WINDOWS

Front, Side and

Rear

Vinyl, commercial grade Schüco windows, black on the exterior and on the

Fiberglass mesh screen included on all operable windows only. Custom glass **Screens**

doors are not fabricated with screens.

Buyer_	 	 	
Date			

10/7/2022 5

Seller Date_

AUDIOVISUAL

SP	E	٩k	(E	R
WI	R	IN	G	

Prewire only. Speakers & volume control hardware not included. Main Level Living Room First Floor

Units

(5) ceiling points, for 5.1 surround, no volume control

Lower Level Family Room First Floor Units

(5) ceiling points, for 5.1 surround, no volume control

Living Room 2nd & 3rd Floor Units

(5) ceiling points, for 5.1 surround, no volume control

Primary Bedroom

(2) ceiling points, with volume control wiring shared with Prmary bathroom

Primary Bathroom

(1) dual ceiling point volume control wiring shared with Primary bedroom (located in Primary bedroom)

NETWORK & CABLE WIRING

Living Room

(1) cable point and (1) electrical outlet installed at elevated wall mount height.

Primary Bedroom

(1) cable point and (1) electrical outlet installed at elevated wall mount height

Family Room 1st Floor Units

(1) cable point and (1) electrical outlet installed at elevated wall mount height

Family Room 3rd Floor Units

(1) cable point installed at baseboard height

Guest Bedrooms

(1) cable point installed at baseboard height

Terraces Duplex

Units

(1) cable point and (1) electrical outlet installed at elevated wall mount height

ELECTRICAL

Wiring

All electrical wiring shall be in accordance with the City of Chicago Building Code.

Equipped with individual circuits.

Smoke & Carbon Detectors

Hardwired and installed in accordance with the City of Chicago Building Code

MECHANICALS

Furnace

Rheem or comparable 90+ high efficiency gas furnace with humidifier

Dual Zones 1st Floor Units

1N, 1E, and 1W has dual zoned heating and cooling.

Buyer	10/7/2022	Seller
Date	6	Date

The **Biazar** Group

Water Heater Duplex units, 50 gallon gas hot water heater, Simplex units, tankless water heater.

Thermostat Nest, Ecobee or comparable

Compressor Locations

At roof level, per plan

Plumbing Service

New 4" water service and sewer from building to main line. All rough plumbing

combination of Copper and PVC

Sprinkler System Sprinkler system, as installed.

Optional All duplexes have gas lines and prepped for optional fireplaces. Price and details,

Fireplace provided upon request.

DRYWALL/ INSULATION

Drywall

To be 5/8" U.S Gypsum or equal on all interior walls and ceilings. Perimeters of all demising partitions to be caulked. Double Drywall between unit ceilings.

Insulation

Exterior Walls: combination of Closed 2" Foam Spray + Batt insulation.

Between Units: Sound Proof R38 Blown In

Roof: Foam, R49

Sound Proofing

1 layer of 1/8" thick, noise coat and noise barrier membrane

1/2 sheet of sound deadening board

Acoustical putty for ceilings and wall penetrations for electrical outlets.

Heavy duty pipe wrap sound insulation for plumbing stacks

Sound insulation and 2" x 4" batt insulation in all bathrooms and mechanical closets.

INTERCOM

Smart Intercom

Dial in intercom system rings to cell phone and provides access to main building entry

door.

EXTERIOR/ COMMON AREAS

Building Exterior Finishes

Front Facade: Modular brick.

Side & Rear Elevations: Utility brick.

Buyer	10/7/2022	Seller
Date	7	Date

The Biazar Group

NORTH CLYBOURN GROUP

Finished with composite decking with steel railings, and equipped with an electrical **Terraces**

outlet and gas.

Exclusive to Units 3E, 3W, 3N, per plan, built out in pressure treated lumber, 4 foot **Roof Deck**

pressure treated lumber divider fencing between units, and equipped with a cable out,

electrical outlet, gas and water.

Exclusive to Units 1N & 2N, per plan, built out in pressure treated lumber, 4 foot **Garage Roof Deck**

pressure treated lumber divider fencing between units, and equipped with an electrical

outlet.

Four millimeter modified bitumen roof Roofing

PARKING

Each unit includes (1) space in garage with remote garage door opener. Garage

GENERAL

Wood doors are subject to movement because of the natural characteristics of wood. Seller's Responsibility for movement of wood doors shall be governed by the standards of the door

Every building is constantly on the move. On a cold, dry day a building will contract. On a hot, moist day a building actually expands. The reason is that cold and dryness cause some materials to contract, while heat and moisture can cause some materials to expand. A building can swell during rain and shrink during a dry spell. SUCH MOVEMENT CHARACTERIZES ALL BUILDINGS AND IS NORMAL AND SHOULD BE EXPECTED. It is possible that movement will have an effect on the walls, ceilings, floors and framing system of your home. It may cause cracking and nail popping in the drywall. The same problem may occur in the flooring system. THEREFORE, WE ARE UNABLE TO GUARANTEE THAT SETTLING, NAIL POPS, CRACKING OF WALLS AND CERAMIC TILE FLOOR WILL NOT APPEAR.

All samples for selection are of actual materials used at 2345 N. Elston Ct. Because of the natural characteristics, production lots, and other circumstances beyond our control, there may be color shade, hue or texture differences between the sample displayed and the materials supplied or installed in your unit. All construction will conform to and meet the building code requirements of the City of Chicago. Certain changes may be dictated by the City's code. Purchaser's signature appearing in these Specifications shall constitute approval and acceptance of all work, if any, already completed as of this date. Acceptance of keys to the building by Purchaser shall constitute formal acceptance and approval of the completed building. Specifications and brand names herein shall be adhered to as closely as possible. However, substitutions may be made by the seller at its sole discretion. Such substitutions shall be of equal or like kind.

Buyer	10/7/2022	Seller
Date	8	Date